HEATING · COOLING · PROPERTY SERVICES

Handled Services LLC

Detroit, Michigan | Phone: _____ | Email: info@handledsvc.com
EIN: 43-2226769 | Licensed & Insured

ESTIMATE

Contractor: Handled Services LLC

Estimate #	**HS-2026-1111-01**
Date	November 11, 2026
Valid through	December 11, 2026
Prepared by	Handled Services LLC
Revision	4

PREPARED FOR (OWNER)

Mark Odom, Property Owner
Phone: 313-639-9373

JOB SITE

5500 Oregon Street
Detroit, Michigan
Two-family flat (duplex) — upper & lower units, full basement

Project Summary

Furnish and install **new high-efficiency gas furnaces for both flats** at 5500 Oregon Street. The building is a two-family flat of **3,200 sq ft** total: upstairs and downstairs flats of **1,600 sq ft each**. Each flat has 4 bedrooms, 2 baths, a kitchen, a dining room and a living room. The building has a full basement, where both furnaces will be installed.

> **Why two furnaces:** Each dwelling unit in a two-family building needs its own heating system. Supply and return air may not be shared between units under the Michigan Residential/Mechanical Code. Separate systems also give each flat its own thermostat and its own gas bill. One shared furnace cannot legally serve both flats.

Design basis (preliminary)

- Detroit outdoor heating design temp: about 6°F; indoor 70°F
- Estimated heat loss: lower flat about 45–55k BTU/h; upper flat (roof & attic exposure) about 60–72k BTU/h
- Final sizing confirmed by Manual J (Item A1) **before** equipment is ordered. If the size changes, the price is adjusted at cost.

Equipment selected

- **Lower flat:** 60,000 BTU input, 96% AFUE (about 57,600 BTU output)
- **Upper flat:** 80,000 BTU input, 96% AFUE (about 76,800 BTU output)
- Sealed-combustion PVC direct vent, ECM blower, MERV 11 filtration, Wi-Fi thermostats

Itemized Estimate

#	Description	Qty	Material	Labor	Amount
A. Design, Permits & Inspections					
A1	Manual J heat-loss calculation & Manual S equipment sizing, both flats (room-by-room)	1 LS	—	$450	**$450**
A2	City of Detroit BSEED mechanical permit — furnace + gas piping (one per flat)	2 ea	$850	—	**$850**
A3	Electrical permit — dedicated furnace circuits	1 LS	$225	—	**$225**
A4	Inspection scheduling & on-site attendance (rough-in + final, each flat)	4 visit	—	$380	**$380**
	Section A subtotal		*$1,075*	*$830*	***$1,905***
B. Removal & Disposal					

#	Description	Qty	Material	Labor	Amount
B1	Shut off & cap gas, disconnect power, remove existing furnace, haul away & dispose	2 ea	$90	$660	**$750**
B2	Remove abandoned metal flue pipe; seal chimney thimble opening	2 ea	$70	$220	**$290**
	Section B subtotal		*$160*	*$880*	***$1,040***
C. Equipment					
C1	**Lower flat:** 60,000 BTU, 96% AFUE gas furnace, single-stage, ECM blower, upflow — Goodman / Rheem / Carrier or equal	1 ea	$2,195	—	**$2,195**
C2	**Upper flat:** 80,000 BTU, 96% AFUE gas furnace, single-stage, ECM blower, upflow — Goodman / Rheem / Carrier or equal	1 ea	$2,395	—	**$2,395**
C3	4″ media filter cabinet, MERV 11, with first filter	2 ea	$330	$160	**$490**
C4	Equipment leveling pad for basement floor	2 ea	$90	$80	**$170**
	Section C subtotal		*$5,010*	*$240*	***$5,250***
D. Venting & Combustion Air (sealed 2-pipe direct vent)					
D1	Schedule 40 PVC exhaust & intake piping, fittings, hangers — up to 25 ft per furnace	2 ea	$370	$520	**$890**
D2	Sidewall termination kit; core-drill brick/masonry wall, sleeve & seal	2 ea	$190	$480	**$670**
D3	**Allowance:** chimney liner & cap for gas water heater(s) left alone in the old chimney (required when the furnace leaves it)	1 allow.	$750	$600	**$1,350**
	Section D subtotal		*$1,310*	*$1,600*	***$2,910***
E. Gas Piping					
E1	Black-iron gas piping from each flat's meter branch to its furnace (up to 20 ft), shut-off valve, sediment trap, connector	2 ea	$420	$750	**$1,170**
E2	Gas pressure test & leak check	2 ea	—	$190	**$190**
	Section E subtotal		*$420*	*$940*	***$1,360***
F. Ductwork & Air Distribution					
F1	Custom-fabricated supply plenum & transition, sealed with mastic	2 ea	$370	$520	**$890**
F2	Return-air drop, filter transition & panning	2 ea	$320	$460	**$780**
F3	Upper flat: tie new furnace into existing supply/return risers through the wall chase	1 LS	$220	$430	**$650**
F4	Seal basement trunk lines & take-offs (mastic / UL foil tape)	2 ea	$130	$460	**$590**
F5	Verify & seal unit-to-unit separation — no supply or return air shared between flats (code)	1 LS	$85	$265	**$350**
F6	**Allowance:** duct repairs found during install (billed at actual cost; unused amount credited back)	1 allow.	$600	$900	**$1,500**
	Section F subtotal		*$1,725*	*$3,035*	***$4,760***
G. Electrical & Controls					
G1	Dedicated 15A/120V circuit from each flat's panel + furnace service switch (licensed electrician)	2 ea	$220	$570	**$790**
G2	Programmable Wi-Fi thermostat — lower flat	1 ea	$165	$85	**$250**

#	Description	Qty	Material	Labor	Amount
G3	Programmable Wi-Fi thermostat — upper flat, incl. new thermostat wire run basement → 2nd floor	1 ea	$185	$260	**$445**
G4	Carbon monoxide alarms (one per flat by sleeping areas + one in basement)	3 ea	$120	$75	**$195**
	Section G subtotal		*$690*	*$990*	***$1,680***
H. Condensate					
H1	Condensate drain line, trap & neutralizer	2 ea	$110	$190	**$300**
H2	Condensate pump (where no floor drain is within reach)	2 ea	$190	$140	**$330**
	Section H subtotal		*$300*	*$330*	***$630***
I. Installation, Start-Up & Cleanup					
I1	Set, level & connect furnace — 2-person crew (licensed lead tech + installer)	2 ea	—	$2,300	**$2,300**
I2	Start-up & commissioning: combustion analysis, gas pressure, temperature rise, static pressure, CO test, owner walkthrough	2 ea	—	$550	**$550**
I3	Floor protection, daily cleanup & final debris haul-off	1 LS	$75	$225	**$300**
	Section I subtotal		*$75*	*$3,075*	***$3,150***

Estimate Total

Section	Amount
A. Design, Permits & Inspections	$1,905
B. Removal & Disposal	$1,040
C. Equipment	$5,250
D. Venting & Combustion Air (sealed 2-pipe direct vent)	$2,910
E. Gas Piping	$1,360
F. Ductwork & Air Distribution	$4,760
G. Electrical & Controls	$1,680
H. Condensate	$630
I. Installation, Start-Up & Cleanup	$3,150

Materials, equipment & fees	$10,765
Labor	$11,920
Michigan sales/use tax on materials	Included
TOTAL ESTIMATE	**$22,685**

Includes allowances totaling $2,850 (chimney liner $1,350; duct repairs $1,500) and permit fees of $1,075. Any unused allowance is credited back on the final invoice.

Optional Add-Ons (not included in total — check to accept)

#	Option	Price	Accept
O1	Upgrade to two-stage 96% AFUE furnace with variable-speed blower (quieter, more even heat)	**$1,150 per flat**	☐ Yes ☐ No
O2	Central air conditioning, 2.5–3 ton, 14.3 SEER2 — condenser, matching coil, line set, pad, disconnect, permit	**$5,450 per flat**	☐ Yes ☐ No
O3	Whole-house bypass humidifier	**$695 per flat**	☐ Yes ☐ No
O4	Add a return-air run to an under-served room	**$395 each**	☐ Yes ☐ No
O5	Professional duct cleaning & sanitizing before start-up	**$425 per flat**	☐ Yes ☐ No
O6	Full replacement of existing ductwork (only if inspection finds it unusable — quoted after Manual D design)	**$6,500–$9,500 per flat**	☐ Yes ☐ No

#	Option	Price	Accept
O7	Extended 10-year labor warranty (registered)	**$595 per flat**	☐ Yes ☐ No

Schedule

- Manual J & permit application: within 3 business days of signed estimate & deposit
- Permit issue (City of Detroit BSEED): typically 5–10 business days
- Installation: **3–4 working days**. Day 1–2: lower flat. Day 2–3: upper flat. Day 4: start-up & commissioning.
- Final inspections scheduled right after start-up

Payment Terms

- **40% deposit** on acceptance (orders equipment, pulls permits): $9,074
- **40%** when both furnaces are set & rough-in passes: $9,074
- **20%** on start-up & passed final inspection: $4,537
- Check, ACH or card (card adds 3% processing fee)

Warranty

- Manufacturer: 10-year parts and lifetime/20-year heat exchanger with online registration. Handled Services registers it for you.
- Handled Services LLC: **2-year labor warranty** on all installation work
- Free 30-day follow-up check of both systems

Owner Responsibilities

- Active gas & electric service in each flat before start-up (DTE)
- Clear access to basement, chimney, both panels & upper-flat wall chase
- Asbestos test results if the house was built before 1980 (see exclusions)

Assumptions

- Each flat is 1,600 sq ft (3,200 sq ft total), as confirmed by the owner.
- Existing supply and return ductwork, including the upper-flat risers, is in usable condition. Minor repairs are covered by the Item F6 allowance.
- Each flat has its own gas meter and electrical panel. Both furnaces go in the basement within 25 ft of an exterior wall.
- A gas water heater left alone in the masonry chimney gets a liner per code (Item D3 allowance). An electric or sidewall-vented water heater means a credit.

Exclusions

- Asbestos/lead testing or abatement. If suspect material is found on old ducts, the old furnace or flue, work stops until it is tested and cleared.
- Gas meter or service changes by DTE; electrical panel or service upgrades
- Plaster/drywall patching and painting beyond fire-caulking at penetrations
- Structural, framing or chimney masonry repair (other than the liner allowance)
- Air conditioning, humidification and full duct replacement unless accepted as options above
- Work outside the scope listed above. Any change is done only by signed change order.

Acceptance

The above prices, scope, assumptions and terms are accepted. Handled Services LLC is authorized to do the work as specified. Payment will be made as outlined above.

Accepted total (base + checked options): $_____

Owner signature — Mark Odom / Date	Handled Services LLC — authorized signature / Date
Printed name: Mark Odom	Printed name & title